



**MUNICIPALITY OF STRATHROY-CARADOC
CARADOC STREET STORM OUTLET**

CONSTRUCTION ADVISORY NOTICE / ROAD CLOSURE – UPDATE

The Municipal Council for Strathroy-Caradoc has awarded the above contract to All Season Excavating Ltd. for the construction. The consulting engineers responsible for the design and site inspection are B.M. Ross and Associates Limited. Construction related activities are scheduled to begin August 26th, 2019 with the installation of sediment and erosion control, steel sheet piling, temporary water servicing, followed by dewatering headers, prior to the underground works installation commencing.

This is the first phase of a major reconstruction project including watermain, sanitary and storm sewers as well as road rebuilding. Boulevard areas within the construction zone will be significantly impacted by construction operations including road widening, pipe and service installations and regrading operations.

ACCESS DURING CONSTRUCTION

Please be advised that during the construction, the Sydenham River Bridge will be closed. However, access to Caradoc Place will be maintained at all times from Front Street and from Garden Lane. Pedestrian traffic across the Sydenham River Bridge will be maintained, for as long as possible, along the east side of Caradoc Street.

Emergency Services, School Bus Operators and Bluewater Recycling Association will be advised of the road closure when the start dates are confirmed.

WATER SERVICING

There will be scheduled water supply disruptions during the work and efforts will be made to keep these disruptions to a minimum. There may be times of unscheduled service disruptions due to unforeseen circumstances. During construction, a temporary water system will be installed to provide potable water service to the Caradoc Place plaza. This temporary system will be tested in accordance with the Ministry of Environment, Conservation and Parks requirements prior to connecting properties to this system. The temporary water system will be buried.

ADDITIONAL INFORMATION

Proprietors should also be aware that in areas of dewatering, pumps must operate 24 hours a day continuously in order to lower groundwater levels for sewer installation. The pump does create noise and best efforts will be made to mitigate the noise. We apologize in advance for any inconvenience from this construction activity. Concerns have also been raised in the past in regard to vibration related to soil compaction. This is a normal construction activity that usually occurs in the course of road rebuilding to ensure that proper compaction is in place thus preventing future settlements.

In the past, concerns have been raised from property owners regarding locate flags/markings on their front lawn. These locate flags should remain in place for the duration of the project as they will assist the contractor in identifying services in the boulevard and to your property.

When construction begins, garbage and blue boxes should be set out for collection by 7:00 AM on your regular day, in the usual location. If required because of the construction, the contractor will get it to the collector and return your receptacles. **Please mark your container(s) with your house number to assure return of the correct containers.**

This is an intrusive construction project that will affect the normal activities of your community. Your cooperation and patience are appreciated.

Plans are available for viewing at the Municipality of Strathroy-Caradoc, Engineering and Public Works Office, 52 Frank Street, Strathroy. For inquiries please call 519-245-1105 ext 270.

Project Contacts

Jeremy VanHaaren
All Season Excavating (General Contractor)
Phone: 519-384-2994

Dave Saundercock
BMROSS Site Representative
Phone: 519-525-0524

George Elliott, P.Eng
Director of Engineering and Public Works
Municipality of Strathroy-Caradoc
Phone: 519-245-1105 ext. 270
Email: gelliott@strathroy-caradoc.ca

